

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>L-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34	●	35		36
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-12: 1/4 Cor. Common to Sec. 34 & 35, T26N-R8W, Boardman Township
1852, GLO resurvey, set post, 10" Hemlock N49E, 35, 10" Hemlock S54W, 11
10-20-1981, Granger Eng. Inc., survey, fd. 1/2" bar, w/accessories, Lib 2, Pg. 680

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-12: 1/4 Cor. Common to Sec. 34 & 35, T26N-R8W, Boardman Township
Fd. 1/2" x 24" R.B. 1.5' East of C.L. Creighton Rd. & 21' South of C.L. Luce Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-12: 1/4 Cor. Common to Sec. 34 & 35, T26N-R8W, Boardman Township
Fd. 1/2" x 24" R.B. 1.5' East of C.L. Creighton Rd. & 21' South of C.L. Luce Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap
Set nail & tag N35W 12" R. Pine, 73.00'
Set nail & tag N42E 32" Maple, 79.42'
Set nail & tag S60E 10" R. Pinc, 47.65'
Set nail & tag S45W P. Pole, 47.17'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 2-3-98



3004849
Page: 1 of 1
02/04/98 11:22A