

SURVEY & REMONUMENTATION

FEB 13 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

KALKASKA
(County)

Located In:

Corner Code #

1997 REMONUMENTATION
1. Public Land Survey

T 26N R 8W
T 25N R 8W

I-13
I-1

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-13 Sec. cor. common to Sec. 34 & 35, T26N-R8W, Boardman Township, Sec. 2 & 3, T25N-R8W, Springfield Twp. 1852, GLO resurvey, set post, 16" Beech N6W, 15, 8" Ironwood N42W, 37 11-20-1973, Granger Eng. Inc., Cert. Survey, w/accessories, Lib. 1, Pg. 470 01-28-1974, J.L. Fletcher #19830, LCR, fd. 1/2" rerod, w/accessories, Lib. 1, Pg. 291

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-13 Sec. cor. common to Sec. 34 & 35, T26N-R8W, Boardman Township, Sec. 2 & 3, T25N-R8W, Springfield Twp. Fd. 1/2" rebar 1' East of C.L. Creighton Rd. & 2' South CL Inman Rd. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-13 Sec. cor. common to Sec. 34 & 35, T26N-R8W, Boardman Township, Sec. 2 & 3, T25N-R8W, Springfield Twp. Fd. 1/2" rebar 1' East of C.L. Creighton Rd. & 2' South CL Inman Rd. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. Set nail & tag N45E 14" Maple 60.68' S74E Rd. Sign post 54.15' Set nail & tag S50W cor. Fence post 47.14' Set nail & tag N54W 32" Maple 44.41'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 2-3-98



3004850
Page: 1 of 1
02/04/98 11:22R