

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>J-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9										●			
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
J-9: Cor. Common to Sec. 23 & 26, T26N-R8W, Boardman Township
 1852, GLO resurvey, set post, 8" Sugar N21E, 16, 10" Beech S51W, 21
 05-19-1903, W.S. Merrill Co. Surveyor, set iron (single prop.) No accessories
 07-06-1989, Farrier Surveying survey, fd. 1 1/4" iron pipe, w/accessories
 Oct. 1989, Farrier Surveying L.C.R., Lib. 2, Pg. 387, fd. 1 1/4" iron pipe, w/accessories
 04-19-1995, Farrier Surveying survey, fd. 1 1/4" iron pipe, w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-9: Cor. Common to Sec. 23 & 26, T26N-R8W, Boardman Township
 Fd. 1 1/4" iron pipe, w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap in C.L. Hall Rd. No GLO witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-9: Cor. Common to Sec. 23 & 26, T26N-R8W, Boardman Township
 Fd. 1 1/4" iron pipe, w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap in C.L. Hall Rd.
 Set nail & tag N05E 6" Apple 51.10'
 Fd. Spike S22W 5" Tw. Elm 25.14'
 Set nail & tag S58W 7" Elm 64.83'
 Fd. Spike N68W P.Pole 99.30' (old witness)

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98



Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 2-3-98



3004853
 Page: 1 of 1
 02/04/98 11:22f
 LB: 5 PG: 257