

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
J-11: Cor. Common to Sec. 26 & 35, T26N-R8W, Boardman Township
 1852, GLO resurvey, set corner. 8" Beech S51W 20, 8" Sugar N20E 35
 05-19-1903, W.S. Merrill, Co. Surveyor, fd. GLO B.Trees, new 9" Hemlock N11W 19 1/2
 09-23-1977, J.L. Fletcher #19830 survey, Lib. 2, Pg. 101, with accessories
 08-18-1989, Farrier Surveying, Cert. of survey, Lib. #3, Pg. 308, fd. iron & cap, w/accessories
 04-19-1995, Farrier Surveying, Cert. of survey, fd. iron & cap, w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-11: Cor. Common to Sec. 26 & 35, T26N-R8W, Boardman Township
 Fd. 1/2" x 18" rebar w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap, cor. falls 7' North of C.L. Woodman Rd. No GLO witnesses found. The Kalkaska Co. Peer group approved and accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-11: Cor. Common to Sec. 26 & 35, T26N-R8W, Boardman Township
 Fd. 1/2" x 18" rebar w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap, cor. falls 7' North of C.L. Woodman Rd.
 Set nail & tag N52W, 14" Maple 19.78'
 North iron & cap #24594 33.00'
 Set nail & tag N60E, 18" Maple 42.32'
 Fd. Spike South, P.Pole 36.95'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98



Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 2-3-98



3004854
 Page: 1 of 1
 02/04/98 11:22F
 LB: 5 PG: 258