

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	<u>T.26N R.8W</u>	<u>K-3</u>
	T. <u> </u> R. <u> </u>	_____
	T. <u> </u> R. <u> </u>	_____
	T. <u> </u> R. <u> </u>	_____
2. Property Controlling in Section	S. <u> </u> T. <u> </u> R. <u> </u>	_____
	S. <u> </u> T. <u> </u> R. <u> </u>	_____
3. Miscellaneous Property in Sec.	S. <u> </u> T. <u> </u> R. <u> </u>	_____
	S. <u> </u> T. <u> </u> R. <u> </u>	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3											●		
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:
K-3: Cor. Common to Sec. 1, 2, 11 & 12, T26N-R8W, Boardman Township
 1852, GLO resurvey, set post, 8" W. Pine S60E, 14, 8" Y. Oak N1W, 16
 07-01-1902, W.S. Merrill, Co. Surveyor, established S.P.M., set pine stake, w/accessories
 11-03-1971, George F. Dely, #5234, survey, noted cor., no accessories, Lib. 1, Pg. 347
 05-1974, J. Wilcox #14102, LCR, fd. RR spike, w/accessories, Lib 1, Pg. 336
 05-1975, J. Wilcox #14102, survey & LCR, fd. RR spike, w/accessories, Lib, 1, Pg. 336
 10-27-1988, Farrier Surveying, survey, fd. RR spike, no accessories
 10-19-1993, Farrier Surveying, survey, fd. RR spike, w/accessories
 08-07-1995, B.M. Jones #23514, survey, fd. RR spike, w/accessories, Lib. 4, Pg. 321



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-3: Cor. Common to Sec. 1, 2, 11 & 12, T26N-R8W, Boardman Township
 Fd. RR spike in C.L. Gregg Road, pulled & replaced with 5/8" x 18" rebar w/brass cap. S.C.M. No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-3: Cor. Common to Sec. 1, 2, 11 & 12, T26N-R8W, Boardman Township
 Fd. RR spike in C.L. Gregg Road, pulled & replaced with 5/8" x 18" rebar w/brass cap. S.C.M.
 Fd. Nail S29E 8" Poplar 85.70'
 Fd. West iron & cap 24594 50.50'
 Fd. Nail N57W 10" Maple 100.10'
 Fd. N05W bolt spike road Pl. 43.45'
 Fd. Spike N16E 8" Poplar 84.92

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98

Signed by Eugene Farrier Date 2-3-98
 Surveyor's Michigan License No. 24594



3004858
 Page: 1 of 1
 02/04/98 11:22f
 Kalkaska County REMON 9 00 1 R 5 PG 262