

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: Corner Code #
(County)
1997 REMONUMENTATION
1. Public Land Survey T 26N R 8W K-9
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____


5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-9: Cor. common Sec. 23, 24, 25 & 26, T26N-R8W, Boardman Township
1852, GLO resurvey, set post, 20" Hemlock N30W, 12, 10" Y. Birch S48E, 35
05-16-1889, E. Mosher Co. Surveyor, Highway Survey, used cor.
04-27-1901, W.S. Merrill Co., Surveyor, fd. Old stake and one G.L.O. bearing tree, set iron stake (buggy axle)
05-19-1903, County Surveyor, fd. Iron (buggy axle)
09-16-1912, County Surveyor, fd. Iron (buggy axle)
09-30-1985, Farrier Surveying, Cert. Survey, fd. 1 1/4" well point pipe, w/accessories
07-06-1989, Farrier Surveying, Cert. Survey, fd. 1 1/4" well point pipe, w/accessories
11-21-1989, Farrier Surveying, Cert. Survey, fd. 1 1/4" well point pipe, w/accessories
10-1989, Farrier Surveying, LCR, fd. 1 1/4" well point pipe, w/accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-9: Cor. common Sec. 23, 24, 25 & 26, T26N-R8W, Boardman Township
Fd. 1 1/4" x 6" pipe on top of axle shaft in C.L. Intersection Of Hall Rd. & Hart Rd. Pulled and replaced with 5/8" x 18" rebar w/brass cap in mon. box. No GLO witnesses were fd. The Kalkaska Co. Peer group approved the above monument as careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-9: Cor. common Sec. 23, 24, 25 & 26, T26N-R8W, Boardman Township
Fd. 1 1/4" x 6" pipe on top of axle shaft in C.L. Intersection Of Hall Rd. & Hart Rd. Pulled and replaced with 5/8" x 18" rebar w/brass cap in mon. box.
Fd. Nail N34E, 16" Tamarack 72.53'
Fd. Nail S33E, 8" Poplar 89.48'
Fd. Nail S28W, 10" Tamarack 102.95'
Fd. Nail N53W, 12" W. Pine 88.25'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98

Signed by Eugene Farrier Date 2-3-98
Surveyor's Michigan License No. 24594



3004864
Page: 1 of 1
02/04/98 11:22f
LB: 5 PG: 268