

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T. <u>26N</u> R. <u>8W</u>	<u>K-11</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Property Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Sec.	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_


5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K11: Cor. Common to Sec. 25, 26, 35 & 36, T26N-R8W, Boardman Township  
 1852, GLO resurvey, set post corner, 14" beech S16E 18, 12" Hemlock N53W, 35  
 08-15-1901, W.S. Merrill, Co. Surveyor, fd. GLO B.T. 8" Beech S16E 32 1/2  
 09-23-1977, J.L. Fletcher #19830 survey, Lib. 2, Pg. 101, with accessories  
 11-17-1981, N.B. DeYoung #20705 survey fd. 1" pipe with accessories  
 08-18-1989, Farrier Surveying, Cert. of survey, Lib. #3, Pg. 308, fd. 1" pipe, with accessories  
 11-04-1992, Farrier Surveying, Cert. of survey, fd. 1" pipe, with accessories  
 05-24-1993, Farrier Surveying, Cert. of survey, fd. 1" pipe, with accessories  
 04-19-1995, Farrier Surveying, Cert. of survey, fd. 1" pipe, with accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
K11: Cor. Common to Sec. 25, 26, 35 & 36, T26N-R8W, Boardman Township  
 Fd. 3/4" pipe w/accessories. Pulled & replaced with 5/8" x 18" re-rod w/brass cap 10' N & 5' W (C.L. to N.) Inter. Of Hart Rd. & Woodman Road. No GLO witnesses fd. The Kalkaska Co. Peer group approved & accepted the above monument as best available evidence of the position of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K11: Cor. Common to Sec. 25, 26, 35 & 36, T26N-R8W, Boardman Township  
 Fd. 3/4" pipe w/accessories, pulled & replaced with 5/8" x 18" re-rod w/brass cap 10' N. & 5' W. (C.L. to N.) Inter. Of Hart Rd. & Woodman Rd.  
 N45W conc. Mon. w/1/2" iron, 43.59'  
 Fd. Nail N45E 38" maple 45.62'  
 Set nail & tag N77E 13" R. Pine, 57.11'  
 Fd. spike S45W 10" J. Pine, 58.29'

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 1-29-98

Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



**3004866**  
 Page: 1 of 1  
 02/04/98 11:22f  
 LB: 5 PG: 270