

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>1-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 15, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3: 1/4 Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township
1852, GLO resurvey, set post, 12" Beech N28E, 12, 9" Beech S76W, 8
06-13-1902, W.S. Merrill, Co. Surveyor, used cor. W/accessories
11-1981, Farrier Surveying, LCR, Fd. E. 1/8 cor. on S. Line & doubled over from a Fd. SE cor. to reset the lost cor., w/accessories, Lib. 2, Pg. 409
07-02-1987, B.M. Jones #23514, Cert. Survey, Fd. Iron bar cap #24594, w/witnesses, Lib. 3, Pg. 129
04-24-1990, Farrier Surveying, survey, Fd. iron & cap #24594, w/accessories, Lib. 3, Pg. 362

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3: 1/4 Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township
Fd. 1/2" iron & cap #24594, pulled & replaced with 5/8" x 18" rerod w/brass cap S.C.M. No GLO witnesses were Fd. The Kalkaska Co. Peer group approved & accepted the above monument as a careful and faithful reestablishment the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3: 1/4 Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township
Fd. 1/2" iron & cap #24594, pulled & replaced with 5/8" x 18" rerod w/brass cap S.C.M.
Fd. North iron & cap #24594 33.03'
Fd. nail S55E, 14" Spruce 58.82'
Fd. nail S10W 36" Maple 47.50'
Fd. nail S50W 12" Birch 64.30'
Fd. nail N53W 7" Poplar 79.62'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 2-3-98



3004870
Page: 1 of 1
02/04/98 11:22
LB: 5 PG: 274