

# SURVEY & REMONUMENTATION

FEB 13 1998

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	<u>T 26N R 8W</u>	<u>M-3</u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
M-3: Sec. Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township  
 1852, GLO resurvey, set post, 24" Hemlock S60W, 49, -18" Hemlock N33W, 09  
 05-16-1887, E. Mosher Co. Surveyor, used for highway survey, no accessories  
 07-01-1902, W.S. Merrill Co. Surveyor, fd. Old stake from B.T. w/accessories  
 06-17-1980, A. L. Dragoo #3921, survey, fd. Iron pipe, w/accessories, Lib. 2, Pg. 565  
 07-02-1987, B.M. Jones #23514, survey, fd. DNR pipe & cap, w/accessories, Lib 3, Pg 129  
 05-12-1987, C.F. Roser #12028, drawing & LCR, fd. DNR mon. W/accessories Lib 2, Pg. 350  
 04-30-1990, Farrier Surveying, Cert. Survey, fd. DNR mon. w/accessories, Lib 3, Pg. 362  
 05-05-1996, Farrier Surveying, Cert. Survey, fd. DNR mon. w/accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-3: Sec. Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township  
 Fd. DNR mon. in C.L. Gregg Rd. To West, left in place. No GLO witnesses were fd. The Kalkaska Co. Peer group approved the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-3: Sec. Cor. Common to Sec. 1 & 12, T26N-R8W, Boardman Township  
 Fd. DNR mon. in C.L. Gregg Rd. To West, left in place. No GLO witnesses were fd.  
 Fd. Nail N42W, 16" W. Pine 53.32'  
 Fd. Nail S48W, 12" W. Pine 87.61'  
 Fd. Nail N50E, 5" W. Pine 21.90'  
 Fd. 5/8" rod w/S.C.M. S03W, 93.06' (Closing corner)

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 1-29-98

Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



**3004878**  
 Page: 1 of 1  
 02/04/98 11:22f