

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on AUGUST 08, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	2
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:
M-5: Sec. Cor. Common to Sec. 12 & 13, T26N-R8W, Boardman Township
 1852, GLO resurvey, set post, 8" Sugar, S80W 26, 10" Sugar, S11W 25
 08-27-1895, E.B. Dennis Co. Surveyor road survey, used cor. W/accessories
 July 1975, J.L. Wilcox #14102, LCR, fd. 1" angle iron w/accessories, Lib. 1, Pg. 355
 03-13-1981, W.B. Batzer #13026, Cert. Survey, fd. Iron w/accessories, Lib. 2, Pg. 641
 01-29-1988, Farrier Surveying, Cert. Survey, fd. 1" angle iron no accessories, Lib. 3, Pg. 475



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-5: Sec. Cor. Common to Sec. 12 & 13, T26N-R8W, Boardman Township
 Fd. 1" angle iron 8' South of C/L Bass Lake Rd. & in C/L Puffer Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-5: Sec. Cor. Common to Sec. 12 & 13, T26N-R8W, Boardman Township
 Fd. 1" angle iron 8' South of C/L Bass Lake Rd. & in C/L Puffer Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap.
 North, Kalkaska Co. Mon. 19.60' (Closing corner)
 Fd. Nail N25E, 32" Maple 44.17'
 Set nail & tag N50E, 7" W. Pine 74.65'
 Set nail & tag S54W, 6" R. Pine 53.62'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 2-3-98