

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA
(County)

Located In:

Corner Code #

1997 REMONUMENTATION

1. Public Land Survey

T 26N R 8W

M-11

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 29, 1997

do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-11: Sec. Cor. Common to Sec. 25 & 36, T26N-R8W, Boardman Township 1852, GLO resurvey, set post, 18" Hemlock S45W, 36, 24" Hemlock N12W, 14 04-27-1901, W.S. Merrill Co. Surveyor, stone cor., no accessories
- 05-20-1981, Farrier Surveying, LCR, fd. Iron raised w/nail, w/accessories, Lib 2, Pg. 292
- 05-20-1981, Farrier Surveying, Cert. Survey, fd. Iron raised w/nail, w/accessories
- 11-17-1981, N. DeYoung, Cert. Survey, fd. 5/8" rod, w/accessories
- 05-28-1987, Farrier Surveying, LCR, fd 1/2" iron, w/accessories, Lib. 2, Pg. 323
- 05-30-1987, Farrier Surveying, Cert. Survey, fd. 1/2" iron, w/accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11: Sec. Cor. Common to Sec. 25 & 36, T26N-R8W, Boardman Township
- Fd. 1/2" iron 1' West of C.L. Puffer Rd., pulled & replaced with 5/8" x 18" rebar, w/brass cap in mon. box. No GLO witnesses were fd.
- The Kalkaska Co. Peer group approved the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11: Sec. Cor. Common to Sec. 25 & 36, T26N-R8W, Boardman Township
- Fd. 1/2" iron 1' West of C.L. Puffer Rd., pulled & replaced with 5/8" x 18" rebar, w/brass cap in mon. box.
- Fd. Nail S77W, P.Pole, 32.77'
- Fd. Nail N68E, 5" W. Pine, 51.10'
- Fd. N89W, 1/2" iron #24594, 33.00'
- Fd. S05W, conc. mon., 211.70' (Closing corner)

**Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County**
Chairman Eugene Farrier
Date 1-29-98

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 2-3-98

3004886
Page: 1 of 1
02/04/98 11:22f