

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-12: East 1/4 Cor. Sec. 36, T26N-R8W, Boardman Township
 1852, GLO resurvey, set post, 10" Beech S10W, 16, 24" Sugar N18E, 18
 04-28-1992, B.M. Jones #23514, Cert. Survey, fd. 1/2" iron, w/accessories, Lib. 4, Pg. 981
 09-08-1992, Grand Traverse Survey Co., Cert. Survey, fd. Iron w/cap P.S.A., w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-12: East 1/4 Cor. Sec. 36, T26N-R8W, Boardman Township
 Fd. 1/2" iron & cap (could not read No. on cap) 5' West of CL Puffer Rd. and 10' North of CL Luce Rd. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-12: East 1/4 Cor. Sec. 36, T26N-R8W, Boardman Township
 Fd. 1/2" iron & cap (could not read No. on cap) 5' West of CL Puffer Rd. and 10' North of CL Luce Rd. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box.
 South, Kalkaska Co. mon. (W 1/4 cor. Sec. 31, T26N-R7W), 238.77' (Closing corner)
 S50W, stop sign post 50.33'
 N77W, road sign post 59.30'
 N25E, tele riser 87.30'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene FARRIER
 Date 1-29-98



Signed by Eugene FARRIER
 Michigan License No. 24594

Date 2-3-98 Surveyor's



3004887
 Page: 1 of 1
 02/04/98 11:22f