

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17-18-19-20

CORNER MONUMENT Drove 1/2 x 12" Iron bar to surface of blacktop

DATE MONUMENT PLACED AND WITNESSED 8/28/67

WITNESSES TO CORNER.....




8" R. Pine S 40 E 51.9'

6" S. Maple S 60 W 167.3'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a survey of Section 17. Set corner at proportionate measurement between 1/4 line fences 1/2 mile east and 1/2 mile west, at county surveyor's record distance from section corner south. This places corner about 2' north of centerline of road, and about 2 rods west of ROW fence north. Previous corner of record was marked by a stone, which we could not recover.



SIGNED *Kenneth J. Ostling* DATE 9/20/67
REGISTERED LAND SURVEYOR #10068