

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7-8-17-18

CORNER MONUMENT Set Cons. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 8/28/67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" J. Pine N 38 E 57.3'

6" Twin R. Pine N 47 W 57.8'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement between corners one mile E-W-S and 1/2 mile north. Unable to locate anything for a previous corner. This point fits streams east and north, and checks good for distance all directions. Fence corner is about 19' S and 17' east, but can find no indication this was established according to survey.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE 9/20/67
REGISTERED LAND SURVEYOR #10068