

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 17-20

CORNER MONUMENT Drove 1/2 x 12" iron bar in blacktop

DATE MONUMENT PLACED AND WITNESSED 8/28/67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" R. Pine S 46 W 60.5'

Cor. fence post North 32.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established in center of E-W county road, in line with old fence north and center of old road grade south.

Occupation would appear to support this location, although no previous corner could be located in road grade. Best available evidence of proper location.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 9/20/67
REGISTERED LAND SURVEYOR #10068