

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 8, 9, 16, 17

CORNER MONUMENT Set Cons. Dept. monument

DATE MONUMENT PLACED AND WITNESSED 8/18/67

WITNESSES TO CORNER.....



18" R. Pine stump N 1 W 47.1'

7" W. Pine West 69.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a survey of Section 17. Found old stake bottom at fence corner. This point checks very well for line and distance south, and appears to conform to U.S. record to other physical monumentation in other directions. Could find no record of a previous corner, and consider this the best available evidence.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 8/28/67
REGISTERED LAND SURVEYOR #10068