

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kalkaska

(County)

Located In:

Corner Code ≠

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>26N</u> R <u>8W</u> | <u>M-3</u> |
| | T <u>26N</u> R <u>8W</u> | <u>M-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl F. Roser, in a field survey on May 12, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 - SE corner of Section 1, fd. Dept. mon. as established by K. Ostling in 1963 Dept. survey (he set it record meas. north of corner to 6 & 7, T26N, R7W, a 3/4" pipe). Ken's notes indicate he had W.S. Merrills 1902 N.B.T, rotted, but in place. RLS Gene Farrier, fd. & used this corner in 1981 survey & sec. subn. of Section 1. Corner falls in open, road, turn-around area; did not set post as post would not last in this area.

M-2 - Fd. L.S. Genne Farrier's 1/2" rod in pipe. Fits 1902 W.S. Merrill survey of Section 1 (incl. section subn.) . Merrill had both U.S. B.T.'s & Farrier's notes indicate one U.S. B.T. possibly still evident.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>M-3</u>			<u>M-2</u>		
Found Department monument			Fd 1/2" reroed w/RLS cap #24594 inside 1 1/2" pipe & set cedar post w/loc tag		
16" White Pine	N42°W	53.3'	W 1/4 Cor, S-6, T26N-		
12" White Pine	S48°W	87.6'	R7W, Set DNR mon.	S03°29'E	21.93'
5" White Pine	N50°E	21.9'	*10" White Pine	N62°E	45.49'
Cor to Sec 5&6			*14" Maple	S78°W	27.12'
T26N-R7W	S03°10'25"E	93.03'	*14" Twin Hemlock	S54°W	36.83'

* = L.S., E. Farrier N.B.T.'s

Signed by Carl F. Roser 8-20-87 Date _____

Surveyor's Michigan License No. 12028

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS

