

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27. NR. 5 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER Witness corner to the
Meander corner between Sec. 17 & 18
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER NBTs to witness corner

8" B. Oak - S81W - 42 1/2 links

20" W. Pine Stump(Orig. BT)

S6W - 16 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set as a witness corner to the true meander corner which would fall in Bear Lake at high water. The Position for the true M.C. is verified by the original BT stump which is still in place with very good face. Stump is at present being undermined by water erosion. Witness corner was placed 25 links north of true corner, in bank about 3 feet above water line.

Corner was placed and witnessed Dec 3, 1956.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 12/5/56