

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>27</u> N. <u>W.</u> R. <u>5</u> <u>W.</u>	G-5; G-6
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 G-5 Recovered 1½"x3' pipe with conc. bottom (Schaaf Monument) and three of his Wits(\*). Corner also fd. & accepted by RLS, Glen DeLaMater in 1978 in survey of Sec. 16. Schaaf notes, 1940 ±, indicate remains of U.S. evidence.

G-6 Recovered 1½"x3' pipe w/ conc. bottom (Schaaf Monument) and three of his Wits (\*). Corner also fd. & accepted by RLS, Glen DeLaMater in 1978 in his survey of Sec. 16. Schaaf notes 1940±, indicate remains of U.S. evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5	G-6
Fd. 1½" pipe & cedar post. Replaced pipe w/ std. Dept. Mon.	Fd. 1½" pipe. Replaced with Std. Dept. Mon. & Ced. Post.
10" Maple N75°E 9.13	10" Tw. Maple N65°W 4.23
11" Tw. Maple N80°W 19.02	3" Beech N50°E 31.83
7" Maple S35°W 9.84	8" Tri. Maple (clump) S15°E 35.32
*40" W. Pine Stp. S27°E 99.7'	*36" W. Pine Stp. N35°W 38.9'
*40" W. Pine Stp. N85°W 185'	*40" W. Pine Stp., Bottom S54°W 28.4'
*a green stone N61°E 32'	*24" W. Pine Stp., Bottom S57°E 21.1'
20"x26"	

SIGNED BY Carl F. Roser 6/19/80 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

KALKASKA COUNTY  
BEAR LAKE TOWNSHIP, North Part