

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*see form  
A-3-B-3 & C-3*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>5</u> R. <u>W.</u>	<u>C-2</u> D-2; D-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Dec. 7, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-2 Recovered D.N.R. Mon. from previous Dept. Survey (1951) which perpetuated Cor. by M. Schaaf. Schaaf notes (1945) indicate U.S.B.T. remains.
  - D-2 Establish Ctr. of Sec. 5 at intersection of 1/4 lines.
  - D-3 Set Std. D.N.R. Mon. by fd. pointed picket bottom from 3 M. Schaaf Wits., still standing. Schaaf had remains of downed Hem., U.S.B.T. remains, in 1943. Fd. Old 1" Pipe, S21°46'W, 101.55.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	C-2	D-2	D-3
Fd. Dept. Mon. & ced. post	Set 3/4" X 54" R. Rod & ced. post w/Loc. Tag.	Set DNR Mon. & ced. post at Schaaf Cor.	
10" Maple N08°E 46.8	12" Maple N77°E 3.1	24" Tw. Maple S60°W 78.6	
10" Maple N22°W 39.9	10" Maple S13°E 26.9	10" B. Cherry N70°W 41.1	
14" Maple S89°W 27.3	9" Maple S48°W 26.2	14" Maple N09°E 70.2	
N-S power line	14" Maple N80°W 29.0	9" B. Cherry N85°E 57.3	
Due W 52'±	1 1/4" pipe S17°33'W 63.55	Ctr, E-W dirt trail	
		Due S 100'±	

SIGNED BY Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_



BEAR LAKE TOWNSHIP  
KALKASKA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_