

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>27</u> N. <u>0.</u> , R. <u>5</u> W.	A-4; A-5; B-1
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____, R. _____ E. _____ S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____, R. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Oct. 12, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-4 Estab. 1/4 Cor. Equidistant & on line btw. fd. Sec. Cor's. to N. & S.
 - A-5 Recovered 1/2" pipe by R.L.S., C. Hughes (#20706) which was set proportionate distance two miles N & S in his Survey of S-18 in 1975. (Certified Boundary Survey Liber 1 Pg. 675).
 - B-1 Estab. 1/4 Cor. on straight line btw. fd. Sec. Cor's. to E & W & in line w/old fn. to N. Fits W.S. Merrill Survey for Sec. 31 of 1922. Cor. fell in Approx. Ctr. of E-W Co. B.Top Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4	A-5	B-1
Set DNR Mon. & ced. post	Fd. 1/2" X 18" pipe.	Drove 1 1/4" X 18" Iron Pin
6" cedar N71°W 19.0	Added DNR Mon. & ced. post	P.Pole N75°E 121.21
8" cedar N04°W 25.7	7" Maple S33°W 18.1	5" Cherry S61°E 112.42
22" W.Pine S04°E 95.9	4" Maple N54°W 14.9	15" Maple S10°W 62.95
⊕ N-S gravel Rd	11" Maple N77°E 40.7	Fd. Schaaf Pipe
Due W 70'+	E-W Trail Due N 103'+	S31°12'W 41.42
		Set ced.post w/Loc.Tag
		Due S 33'

SIGNED BY Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

BEAR LAKE TOWNSHIP
KALKASKA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____