

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>●</u> , R. <u>5</u> W. <u>●</u>	H-3; I-2; I-3; J-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Oct. 12, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. -Description of original monument and accessories and/or subsequent restoration:

C. (continued) I-3
 Fd. Schaaf Mon. Replaced with
 DNR Mon. & ced. post
 11" Maple N13°E 12.5
 13" Cherry N82°W 21.6
 9" Maple S15°W 16.9
 10" Maple S65°E 30.4
 Fd. 1 1/2" Pipe
 N41°17'W 70.87

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-3 Re-estab. 1/4 Cor. equidistant & on line between Sec. Cor's to E & W. Schaaf Cor. way out of position E & W.
 I-2 Recovered M. Schaaf Mon., whose notes (1944) indicate he had U.S.B.T. sites.
 I-3 Recovered M. Schaaf Mon. (1 1/4" pipe w/sq. conc. base) whose notes (1943) indicated he had U.S.B.T. sites. Schaaf notes also indicate 1 1/2" pipe NW as fd. during this survey. We drove 1 1/2" pipe flush with ground.
 J-3 Re-establish 1/4 Cor. Equidistant & on line between fd. Sec. Cor's to E & W. Schaaf position (no good) per (3) of his wits. would be N53°57'W, 29.9'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3	I-2	J-3
Set DNR Mon. & ced. post	Fd. Schaaf Mon. & added DNR	Set DNR Mon. & ced. post
10" Maple S55°W 12.6	Mon. & ced. post	11" Maple N55°W 15.7
9" Maple N40°W 5.2	9" Maple S38°E 6.2	8" Cherry S46°W 38.1
8" Maple N34°E 22.4	10" Maple N72°E 20.6	5" Ironwood S37°E 35.8
8" Y. Birch S72°E 17.4	7" Maple N58°W 23.6	23" Hemlock N84°E 28.4
Schaaf 1 1/4" pipe (cut off & buried same) S70°24'E 28.1	9" Maple S84°W 16.9	
	N-S random Due W 8.8	

SIGNED BY Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BEAR LAKE TOWNSHIP
KALKASKA COUNTY