

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>5</u> W. <u>●</u>	G-1; G-2; G-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 10, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-1 Recovered 1 1/4" pipe used by R.L.S., J. Fletcher in his survey of Sec. 4. Fd. M. Schaaf pipe is S02'16"E, 142.37'; cut pipe off flush w/ground. Note: Fd. 1 1/4" pipe is in approx. ctr. of E-W black top rd. (Co. Rd. 612), with approx ctr. of black top rd to N. (Blue Lake Rd.) being 3'+W.
- G-2 Recovered 1/2" rod as set by R.L.S., J. Fletcher (#19830) from fd. M. Schaaf Wits. & used to subdivide S-4. Schaaf notes (1944) indicate he had U.S.B.T. sites.
- G-3 Recovered 1/2" rod as set by R.L.S., J. Fletcher (#19830) from fd. M. Schaaf Wits. Schaaf had U.S.B.T. sites, (1944).


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1	G-2	G-3
Fd. 1 1/4" pipe in rd. intersection	Fd. 1/2" X 24" rod & replaced with DNR Mon. & ced. post	Fd. 1/2" X 24" re-rod; Replaced w/DNR Mon & ced. pos
Power Pole N40°E 51.72	8" Iron Wood N40°E 31.6	8" Maple N52°E 26.91
16" Bass Wood S53°E 83.98	6" Maple S82°E 16.50	14" Cherry N22°W 39.3
10" Maple S12°W 36.45	9" Maple S64°W 3.20	19" Maple N64°W 34.73
S.E. Cor of Sub. Station Fn. N35°W 56.3	10" Tw. Cherry N25°W 34.12	15" Cherry S45°W 25.8
Set ced. post w/loc. tag Due S. 33'		

SIGNED BY Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BEAR LAKE TOWNSHIP  
KALKASKA COUNTY