

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> N. <u>5</u> R. <u>W.</u>	C-1; D-1; E-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 19, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1 Fd. & accepted 1/2" re-rod by Fletcher which fits W.S. Merrill Survey of Sec. 31 (28-5), Book 33, Pages 105-107, dated 1922.
- D-1 Etab. 1/4 Cor. equidistant & on line btw. fd. Sec. Cor's to E & W. Schaaf Cor. set down flush w/ground.
- E-2 Recovered 1/2" rod as set by R.L.S., J. Fletcher (#19830) from fd. M. Schaaf Wits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1	D-1	E-2
Fd. 1/2" re-rod in ctr. E-W B.Top Rd.	Drove 1 1/4" X 20" Iron Rod in B.Top Rd.	Fd. 1/2" pipe & added DNR Mon. ced.post
16" Maple N25°E 110.23	7" Maple S51W 90.75	12" Oak N22°W 37.9
7" Maple S39°E 99.17	8" Maple S43°E 48.19	10" Tw.B.Cherry N79°E 33.2
7" Maple S55°W 111.20	8" Maple N05°W 109.45	12" B.Cherry S37°E 90.3
Set ced.post w/Loc. Tag N45°E 60'	Fd. Schaaf 1 1/2" pipe S40°09'W 57.97	
Ctr. of rds to N & S are 4'+W	Ctr. E-W B.Top Rd. Due N 5'+ Set ced.post Due S 28'---	

SIGNED BY Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BEAR LAKE TOWNSHIP
KALKASKA COUNTY