

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                          | LOCATED IN--:                                | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>27</u> N. <u>6</u> , R. <u>5</u> W.    | A-1; <u>A-2</u>    |
| 2. PROPERTY CONTROLLING IN SECTION _____   | , T. _____ N. _____ S., R. _____ E. _____ W. | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____ S., R. _____ E. _____ W. | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |  |                    |
| 5. PRIVATE CLAIMS _____                    |  |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Oct. 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-1 B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Four Twp. Corner, T27 & 28N-R5 & 6W; Fd. R.R. Spk. in Co. Rd. 612 (B.Top rd E&W) which fits 1919 Wit. by B.L.Caukin (Notes at Antrim Co. Rd. Comm.) and some Wit. at Kalkaska Co. Reg. of Deeds, large black & brown Co. Survey Record #1, Page 68-A; W.S.Merrill, Sept. 1920; Sug. 12, S16°W, 1.76 chains. Ctr. E-W B.Top Rd., due S., 3'+. Ctr. N-S gravel rd., due W., 112+ Fn. line North, due E., 73'+.
- A-2 Recovered 1 1/4" pipe by M.Schaaf, who had U.S.B.T. remains in 1945. Fletcher used this corner to sub-divide Sec. 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| A-1                        | A-2                         |
|----------------------------|-----------------------------|
| Fd. RR Spk. Replaced       | Fd. Schaaf Mon replace with |
| w/1 1/4" X 18" Iron pin    | DNR Mon. & ced. post        |
| 20" W.Pine N51°E 96.51     | 25" W.Pine N72°E 116.56     |
| 10" Maple S52 E 132.96     | 17" Cherry S15°W 65.85      |
| NE Cor. of Sub.Station Fn. | 11" Cherry S63°W 56.97      |
| S11°W 41.7                 | 11" W.Pine N33°W 25.00      |
| 33" Maple S16°W 116.43     | N-S gravel Rd.Due W 150'+   |
| Set ced.post w/Loc.Tag:    |                             |
| Due S 36'                  |                             |

SIGNED BY Carl F. Roser DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BEAR LAKE TOWNSHIP  
KALKASKA COUNTY