

LANSING Forestry

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

KALKASKA

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>6</u> T. <u>27</u> N. R. <u>5</u> W.		<u>G-2, C-3, B-3</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

File # 297

STATE OF MICHIGAN  
COUNTY OF KALKASKA } CS

FILED 13th DAY OF  
Feb. 9 A. D. 19 74 AT 9:00  
O'CLOCK A. M.

*Marshall J. Metz*  
REGISTER OF DEEDS

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, James L. Fletcher do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 27 19 74, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

*SEC. 6* SE Cor. was re-established by proportionate measurement.  
*SEC. 6* S $\frac{1}{4}$  Cor. located by DNR, Traverse City Office.  
 DNR-Replaced Fd. 2"x4" Pine Stub (old M. Schaaf Cor.)  
 with Std. DNR Mon. and Ced. Guard Post.  
 C. Roser ~ R.L.S. #12028, Sept. 1974  
 (Note: Schaaf Cor. was recovered by C. Roser in Jan. 1974)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>S<math>\frac{1}{4}</math> Cor. SEC. 6</u>	<u>SE Sec. Cor. SEC 6</u>
Fd. 2"x4" Pine Stub	Set $\frac{1}{2}$ " Re-rod
Nail in 12" White pine N10 <sup>0</sup> W 63.36'	Nail in 18" Twin Oak S60 <sup>0</sup> W 73.03'
Nail in 9" White Pine S45 <sup>0</sup> W 79.59'	Nail in 22" Red Pine N45 <sup>0</sup> W 61.81'
Nail in 10" White Birch S10 <sup>0</sup> E 63.15'	Nail in 10" Aspen N40 <sup>0</sup> E 95.70'
<u>East <math>\frac{1}{4}</math> Cor. SEC. 6</u>	
Fd. 4" Brass Cap	
Nail in Powerpole S60 <sup>0</sup> W 56.47'	
Nail in 4" Twin Maple N35 <sup>0</sup> W 26.37'	
Nail in 6" Twin Apple S70 <sup>0</sup> E 58.53'	

NOTE: DNR will set standard mon. at S $\frac{1}{4}$  cor. in Spring, 1974.


SIGNED BY James L. Fletcher DATE January 28, 1974

SURVEYOR'S MICHIGAN REGISTRATION NO. 19830

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO \_\_\_\_\_