

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- |                                      |   |            |   |           |            |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey                | T | <u>27N</u> | R | <u>5W</u> | <u>L12</u> |
|                                      | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section   | S | _____      | R | _____     | _____      |
|                                      | S | _____      | R | _____     | _____      |
| 3. Miscellaneous Property in Section | S | _____      | R | _____     | _____      |
|                                      | S | _____      | R | _____     | _____      |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on September 9, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		●		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L12 - G. Henning - 1961 - Drive shaft  
 Old NBT 10" J. Pine N70°W 42.6'  
 Nail in base 5" J. Pine N7°E 23.05'  
 Nail in base 10" J. Pine S39°W 21.9'  
 - Rec. Sur. - L1, P.479 - R.T. Ostling - 1974  
 Drive shaft - same wit. as Henning.  
 - Rec. Sur. L.3, P. 77 & 88 - N. Parker - 1986  
 1 1/4" gear shaft

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

- L12 - Center 1/4, Sec. 36 - Fd. 1 1/4" iron drive shaft of record.  
 The calculated intersection of the 1/4 lines is 0.79' S and 0.57' W.  
 Accepted 1 1/4" drive shaft as the best available evidence of the position of the corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L12 - 1 1/4" iron drive shaft  
 N2°W 15.51' to set N & T in W side 11" J. Pine  
 S70°E 22.21' to set N & T in N side 6" Tw. Maple  
 S6°W 28.11' to set N & T in E side 12" B. Oak  
 S43°W 21.60' to set N & T in S side 14" J. Pine (GH, RTO)  
 N77°W 16.26' to set N & T in S side 5" W. Pine  
 Set Blue Carsonite Post w/ Loc. tag 1' W

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 4/11/2001