

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S 36	T 27N	R 5W 10
	S 36	T 27N	R 5W 12
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on September 9, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

10 - None

12 - Unrec. Sur. - N. Parker - 1986

1/2" x 18" iron bar
Spike in 8" J. Pine N55°E 18'
Spike in 24" J. Pine N57°W 48'
Axel shaft is 5.7' N & 8' E

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

10 - S 1/16 common to Sec. 35 & 36

Set 2" alum. Cap on 5/8" x 34" rebar per standard BLM procedure. Falls on SE'ly side of 6" cedar anchor post for fence remains W & S.

12 - CS 1/16 Cor. Sec. 36 - Didn't find Parker's 1/2" x 18" iron bar.

Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure. Fits 2 Parker Wit. closely. Corner falls in sand driveway. CL. of sand rd. NE-SW is 22' NW'ly.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10 - 2" AC on 5/8" x 34" rebar

Set Blue Carsonite Post w/ loc. tag 1' NE
N51°W 20.51' to N & T in NE side 11" Cedar
N27°W 31.70' to N & T in SW side 11" Cedar
S39°W 7.94' to N & T in W side 17" R. Maple
N45°E 31.78' to N & T in SE side 5" W. Pine

12 - 2" AC on 5/8" x 34" rebar - down 0.4'

North 102.01' to set 2" alum. Cap on 5/8" x 34" rebar on line w/ Blue Carsonite post w/ loc. tag 1' W.
N46°10'E 9.48' to Fd. axel shaft w/ 1 1/2" I.D. Pipe on W. side (NP)
N58°W 48.50' to set N & T in NE side Tw. 13" J. Pine (NP)
S12°W 15.22' to set N & T in W side 11" R. Pine
S62°E 156.38' to SW cor. Blk. FNDD. HSE #1811

Signed by:

Craig W. McVean

Date:

4/11/2001

Surveyor's Michigan License No.:

39088

