

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

97 JAN 31 PM 2: 26

Jean Hall
REC'D DEEDS

for corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1996 REMONUMENTATION Public Land Survey	T <u>27N</u> R <u>6W</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on Nov. 12, 1996,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:
A-12 cor common to Sec. 31, T27N-R6W, Excelsior Township & Sec. 36,
T27N-R7W Kalkaska Township
1850, G.L.O. resurvey, Set Post. 10" Cedar S59W 16, 8" Cedar N80W 12.
1888, E. Mosher, Co. Surveyor, used corner, no accessories.
11-10-1972, C.L. Roser, fd old stake set DNR mon, no accessories
11-10-1972, LCRC Liber 1 pg. 182.
09-24-1973, J.R. Radcliffe, fd DNR mon. Liber 1 pg. 443 of Survey.
09-24-1973, LCRC Liber 1 pg. 282.
09-17-1981, N.F. Parker, fd DNR mon. Liber 2 pg. 824 of Survey.
06-18-1983, E.D. Farrier, Survey #2583, fd DNR mon, w/ accessories.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-12 cor common to Sec. 31, T27N-R6W, Excelsior Township & Sec. 36,
T27N-R7W Kalkaska Township
Found DNR Mon w/ DNR Post, left in place. No G.L.O. witnesses found. The
Kalkaska Co. peer group approved & accepted the above monument as a
careful and faithful perpetuation of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-21-97

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-12 cor common to Sec. 31, T27N-R6W, Excelsior Township & Sec. 36,
T27N-R7W Kalkaska Township. Found DNR Mon w/ DNR Post, left in place.
Found nail N85W 7" Hemlock, 13.22'
Found nail S02E 14" Hemlock, 40.32'
Found nail S75E 12" Cedar, 36.60'
Set nail East 4"x4" Cedar Post, 1.25'



Signed by Eugene Farrier Date 1-30-97
Surveyor's Michigan License No. 24594