

**SURVEY & REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN  
RECEIVED

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 23 AM 9:14

*Jean Hall*  
REG. OF DEEDS

corners in **SECTION**

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION Public Land Survey	T <u>27N</u> R <u>6W</u>	C-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on NOV. 12, 1994,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
rent manual of survey instructions of the United States Department of the Interior, Bureau of Land  
agement or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
ve were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
irt of Law; established, re-established, monumented, re-monumented, recovered, found as  
ressed below:

**TE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- C-9: Cor. common to Sec. 19, 20, 29 & 30, T27N-R6W
- 1850 GLO re-survey: set post, Beech 14", S40E, 40, Hemlock 12", N40W, 5
- 5-21-1875, D.E. McVee, noted cor., no accessories
- 6-4-1888, E. Mosher, noted cor., no accessories
- 12-26-02, W.S. Merrill, noted cor., no accessories
- 1936, MDOT, Right-of-way Map, noted cor., no accessories
- 9-19-73, LCRC(L.L. Cavanagh), fd bar fence cor., w/access, Lib 1 Pg 254
- 5-2-74, LCRC(D.E. Porter), fd PK nail, w/accessories, Lib 1 Pg 314
- 9-9-77, N.F. Parker, fd PK nail, w/accessories, Lib 2 Pg 84
- 3-31-78, J.L. Fletcher, fd 1/2" rod in Mon. box, w/access, Lib 2 Pg 185
- 11-11-80, J.L. Fletcher, fd iron in Mon. box, w/access., Lib 2 Pg 599
- 5-17-85, E. Farrier, fd 1/2" iron in Mon. box, w/access.,
- 2-93, Wilcox Assoc., fd 1/2" bar in Mon. box, w/access.,

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9: Cor. common to Sec. 19, 20, 29 & 30, T27N-R6W  
Fd 1/2" x 18" R.B. Pulled & set 5/8" x 18" R.B. w/brass cap in Mon. box in  
C.L. M-72 & Crawford Lake rd., 0.4' below rd. surface. No GLO witness  
were fd.

On 12-20-94 the Kalkaska Co. peer group approved the above monument as a  
careful and faithful reestablishment of the position of the original  
corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-22-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-9: Cor. common to Sec. 19, 20, 29 & 30, T27N-R6W
- Fd 1/2" x 18" R.B. Pulled set 5/8" x 18" R.B. w/brass cap in Mon. box in  
C.L. M-72 & Crawford Lake rd., 0.4' below rd. surface.
- S04E, 59.92', fd nail & tag Ancor. Pole
- S37W, 60.38', fd nail & tag P.Pole
- N30W, 80.38', fd nail & tag R. Pine
- N20E, 84.20', fd nail & tag Cor. con slab



ed by *Eugene Farrier*

Date 12-22-94

eyor's Michigan License No. 24594