

**SURVEY &
REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN
RECEIVED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 23 AM 9:18

corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION	T <u>27N</u> R <u>6W</u>	<u>D-11</u>
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on NOV. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

D-11: Cor. common to Sec. 29 & 32, T27N-R6W
1850 GLO re-survey: set post, Beech 14", N55W, 28, Sugar 18", S35E, 18
11-9 & 12-7-04, W.S. Merrill, fd iron stake for cor., no accessories.
Unknown date, Kalkaska Co Rd Comm, fd 1 1/4" pipe, w/accessories
6-15-74, W. Downey, fd cor., no accessories
6-19-74, F.C. Wagenschutz, fd plastic cap #12026, also fd 1/2" rod
inside old 1 1/2" pipe. No accessories

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11: Cor. common to Sec. 29 & 32, T27N-R6W
Fd 1/2" x 18" iron, pulled & set 5/8" x 18" R.B. & brass cap 0.4' below
surface & in C.L. Tyler Rd. No GLO wit were fd.
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a
careful and faithful reestablishment of the position of the original
corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11: Cor. common to Sec. 29 & 32, T27N-R6W
Fd 1/2" x 18" iron, pulled & set 5/8" x 18" R.B. & brass cap 0.4' below
surface & in C.L. Tyler Rd. No GLO wit were fd.
South, 31.05', set nail P. Pole
S35E, 45.20', set nail 8" R. Pine
S55E, 70.00', 10" R. Pine
North, 32.97', P. Pole



Recorded by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-94