

**SURVEY & REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 23 AM 9:21

corners in

ALASKA	Located In:	Corner Code #
(County)		
1994 REMONUMENTATION		
Public Land Survey	T 27N R 6W	E-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on NOV. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- E-9: Cor. common to Sec. 20, 21, 28 & 29, T27N-R6W
- 1850 GLO re-survey: set post, Beech 10", N85E, 40, Sugar 20", S84W, 30
- 7-1-1876, D.E. Mc Vee, noted cor., no accessories
- 6-4-1888, E. Mosher, noted cor., no accessories
- 12-4-02, W.S. Merrill, fd old cor., set cedar stake, no accessories
- 1-6-03, W.S. Merrill, notes cor. as cedar stk., no accessories
- 1936, MDOT, Right-of-way map, notes cor., no accessories
- Kalkaska Co Rd Comm, fd iron in ctr of int., w/access.
- 1955-56, K.J. Ostling, notes iron in pvt., no accessories
- 9-19-73, LCRC(L.L. Cavanagh), fd R.R. spike, w/accessories, Lib 1 Pg 254
- 12-15-73, LCRC(W.E. Ross), fd 1/2" iron, w/accessories, Lib 2 Pg 27
- 9-12-74, C.J. Hughes, fd R/R spike, no accessories, Lib 1 Pg 967
- 6-12-75, J.L. Fletcher, fd R/R spike, no accessories, Lib 1 Pg 670
- 7-18-77, J.L. Fletcher, fd RLS cap #20706, w/accessories, Lib 2 Pg 93
- 10-28-83, E. Farrier, fd R/R in Mon box, w/accessories, Lib 2 Pg 800
- 12-11-92, E. Farrier, fd B. spk. in mon box, w/accessories,
- 2-93, Wilcox Assoc., noted cor., w/access.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-9: Cor. common to Sec. 20, 21, 28 & 29, T27N-R6W
- Fd 5/8" x 18" re-rod, pulled & set 5/8" x 18" R.B. & brass cap 2.5' S.
- C.L. M-72, in C.L. N. S. No GLO witnesses were fd
- On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9: Cor. common to Sec. 20, 21, 28 & 29, T27N-R6W
- Fd 5/8" x 18" re-rod, pulled & set 5/8" x 18" R.B. & brasscap 2.5' S. C.L.
- M-72, in C.L. N. S.
- N30W, 65.68', Ctr C.P R. marker
- N33E, 76.78', fd nail P. Pole
- S38E, 57.55', fd nail P. Pole
- N38W, 83.05', fd nail P. Pole

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-20-94



by *Eugene Farrier*

Date 12-22-94

Surveyor's Michigan License No. 24594