

**SURVEY &  
REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN  
RECEIVED

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 23 AM 9:21

corners in

<u>ALKASKA</u> (County)	Located In:	Corner Code #
1994 REMONUMENTATION	T 27N R 6W	E-10
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER in a field survey on NOV. 12, 1994  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

E-10: Cor. common to Sec. 28 & 29, T27N-R6W  
1850 GLO re-survey: set post, Beech 8", N50W, 35, Beech 6", S58E, 21  
7-1876, D.E. McVee, noted cor., no accessories  
12-4-02, W.S. Merrill, fd 1 bearing trio of Gov. Resurvey & set Cedar post, no access  
1-6-03, W.S. Merrill, noted cor., no accessories  
2-1956, K.J. Ostling, noted cor., w/access.  
Kalkaska Co Rd Comm, fd 1 1/2" iron, w/access.,  
12-15-73, LCRC(W.E. Ross), fd 3" iron, w/access., Lib 2, Pg 27  
9-74 to 9-93, Certificates of Survey, all fd 1/2" pipe w/ 3/4" x 2' iron below surface, C.J. Hughes(Lib 1 Pg 967), J.L. Fletcher(Lib 1 Pg 670), E. Farrier(fd cor. w/access.)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10: Cor. common to Sec. 28 & 29, T27N-R6W  
Fd 1/2" x 18" iron & cap inside 2" x 12" iron pipe. Pulled both & set 5/8" x 18" R.B. & brass cap in Mon. box 1' w. C.L. Sigma rd. & 0.4'. Below surface. No GLO wit. were fd  
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *[Signature]*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10: Cor. common to Sec. 28 & 29, T27N-R6W  
Fd 1/2" x 18" iron & cap inside 2" x 12" iron pipe. Pulled both & set 5/8" x 18" R.B. & brass cap in Mon. box 1' w. C.L. Sigma rd. & 0.4' below surface.

S33E, 61.05', fd nail P. Pole  
S35W, 54.40', fd nail P. Pole  
N45W, 40.10', fd nail P. Pole  
N27E, 95.05', fd nail P. Pole  
N41W, 4.45', 3/4" x 2" iron



Recorded by *[Signature]*

Date 12-22-94

Surveyor's Michigan License No. 24594