

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN
RECEIVED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Joan Hall
REG. CLERK

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #:
1996 REMONUMENTATION	T <u>27N</u> R <u>6W</u>	<u>E-12</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER in a field survey on Sept. 27, 19 96
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- E-12 cor common to Sec. 32 & 33 T27N-R6W, Excelsior Township
1852, GLO resurvey, Set Post. 6" Beech S40W 28, 14" Sugar N22E 19.
1888, E. Mosher, Co. Surveyor, used corner, no accessories.
- 09-02-1903, W.S. Merrill, Co. Surveyor, used corner, Gov. Surv. Bearing trees.
- 11-09-1904, W.S. Merrill, Co. Surveyor, used corner, no accessories.
- 06-12-1986, N.B. DeYoung, fd 1" bolt. Liber 3 pg. 280.
- 04-25-1979, LCRC Liber 2 pg. 177.
- 04-25-1979, J.L. Fletcher, fd 1" bolt. Liber 2 pg. 345.
- 10-19-1982, K.J. Ostling, fd bolt, no accessories.
- 05-22-1990, Farrier Surveying, Survey #6490, fd 1" sq. bolt, no accessories.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 cor common to Sec. 32 & 33 T27N-R6W, Excelsior Township
Found 1" iron bolt (hollow) 10" long w/ accessories, then found old plow blade. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 2' West of centerline of Siema Road (Co. Rd. 571). No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

**Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County**

Chairman *Eugene Farrier*

Date 1-21-97

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 cor common to Sec. 32 & 33 T27N-R6W, Excelsior Township
Found 1" iron bolt (hollow) 10" long w/ accessories, then found old plow blade. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 2' West of centerline of Siema Road (Co. Rd. 571).
Set nail & tag West 45" Maple, 35.88'.
Set nail & tag N58E 14" Beech, 76.13'.
Set nail & tag S35E Power Pole, 62.80'.
Set nail & tag S50W 13" Maple, 51.50' fd old wit nail & tag #2937.

Signed by *Eugene Farrier*

Date 1-30-97

Surveyor's Michigan License No. 24594

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 2, 1997
REVISOR 3/2/93

