

**SURVEY & REMONUMENTATION**

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

CORNER RECORDATION CERTIFICATE 1994 DEC 23 AM 9:23

Filing Requirement of Act 74, Mich. P.A. 1970

*Jean Hall*  
REG. OF DEEDS

corners in

**SECTION**

(KALKASKA County)	Located In:	Corner Code #
1994 REMONUMENTATION		
Public Land Survey	T 27N R 6W	F-9
	T R	
	T R	
	T R	
Property Controlling	S T R	
In Section	S T R	
Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

EUGENE FARRIER, in a field survey on NOV. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the rent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

F-9: Cor. common to Sec. 21 & 28, T27N-R6W  
1850 GLO re-survey: set post, Sugar 12", S22W, 33, Beech 10" N50E, 33  
12-4-02, W.S. Merrill, noted cor., no accessories  
1-6-03, W.S. Merill, established cor., no witnesses  
1936, MDOT, Right-of-way map, noted no cor. shown, no accessories  
1955, K.J. Ostling, noted cor., no accessories,  
7-18-77, J.L. Fletcher, fd R.L.S. cap #20706, w/accessories, Lib 2 Pg 93  
2-93, Wilcox Assoc., fd B&C, w/accessories,

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9: Cor. common to Sec. 21 & 28, T27N-R6W  
Fd 1/2 rebar w/cap. Pulled and replaced with 5/8" x 18" rebar w/brass cap. No G.L.O. wit. fd.  
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman *Eugene Farrier*  
Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9: Cor. common to Sec. 21 & 28, T27N-R6W  
Fd 1/2 rebar w/cap. Pulled and replaced with 5/8" x 18" rebar w/brass cap.  
South, 62.73', fd iron & cap #28432  
S20E, 86.80', fd nail 28" Maple  
N53E, 89.10', fd nail Power Pole  
N88E, 42.50', fd nail 5" R. Pine



Surveyed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-94