

**SURVEY &
REMONUMENTATION**

KALKASKA COUNTY, MICHIGAN
RECEIVED

MAR 21 1997

LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 2:26

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1996 REMONUMENTATION	T <u>27N</u> R <u>6W</u>	<u>F-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

EUGENE FARRIER in a field survey on July 8, 1996,
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Description of original monument and accessories and/or subsequent restoration:

F-11 cor common to Sec. 28 & 33, T27N-R6W, Excelsior Township
1852, GLO resurvey, Set Post. 8" Sugar S40E 35, 8" Sugar N22W 31.
12-04-1902, W.S. Merrill, Co. Surveyor, used corner, w/ accessories.
09-02-1903, W.S. Merrill, Co. Surveyor, used corner, w/ accessories.
1955, K.J. Ostling, used corner, no accessories.
07-19-1971, LCRC Liber 1 pg. 19.
12-17-1971, J.L. Wilcox, used corner, no accessories.
07-21-1992, N.L. Way, used corner, no accessories.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 cor common to Sec. 28 & 33, T27N-R6W, Excelsior Township
Found 1/2" iron & cap #14102 w/ accessories. Pulled & Set 5/8" x 36"
re-rod w/ Alum. cap 4' East of fence to South & 6' South of East-West
2-Track. No G.L.O. witnesses were found. The Kalkaska Co. peer group
approved & accepted the above monument as the best available evidence of
the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-31-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 cor common to Sec. 28 & 33, T27N-R6W, Excelsior Township
Found 1/2" iron & cap #14102 w/ accessories. Pulled & Set 5/8" x 36"
re-rod w/ Alum. cap 4' East of fence to South & 6' South of East-West
2-Track.
Set nail & tag N40E 20" Maple, 18.32'
Set nail & tag East 12" Tw Maple, 37.94'
Set nail & tag S55E 12" Maple, 33.75'
Set nail & tag S18E 14" Maple, 42.26'



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594