

SURVEY & REMONUMENTATION

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:23

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Jean Hall
REG. OF DEEDS

SECTION

corners in

KALKASKA (County)	Located In:	Corner Code #
1994 REMONUMENTATION	T 27N R 6W	G-7
Public Land Survey	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

EUGENE FARRIER, in a field survey on NOV. 12, 19 94, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the rent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 G-7: Cor. common to Sec. 15, 16, 21 & 22, T27N-R6W
 1850 GLO re-survey: set post, Sugar 12", S10W, 25, Sugar 12" N14E, 29
 8-17-1888, E. Mosher, noted cor., no accessories
 1955, K.J. Ostling, noted cor. not fd, no accessories
 8-5-70, Kalkaska Co Rd Comm, fd shaft w/3 cor. connect. on end & placed cabin spike on top to bring to gravel grade, w/accessories
 8-28-73, LCRC(L.M. Gerschbacher), fd cabin spike over cor., w/access, Lib 1 Pg 242
 8-20-74, LCRC(H.L. Fluharty), fd spk at rd int., w/access, Lib 1 Pg 325
 6-18-79, J.L. Fletcher, fd 1/2" bolt spike, w/access, Lib 2 Pg 353
 4-21-83, N.B. DeYoung, fd 1/2" iron, w/accessories, Lib 2 Pg 761

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7: Cor. common to Sec. 15, 16, 21 & 22, T27N-R6W
Fd 3 cor. 3/4" x 48" iron shaft raised w/12" cabin spk. Pulled both & set 5/8" x 36" R.B. in mon. box in C.L. rd. int. & 0.4' below surface. No GLO wit. were fd

On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7: Cor. common to Sec. 15, 16, 21 & 22, T27N-R6W
 Fd 3 cor. 3/4" x 48" iron shaft raised w/12" cabin spk. Pulled both & set 5/8" x 36" R.B. in mon. box in C.L. rd. int. & 0.4' below surface
 N36W, 49.84', fd nail P. Pole
 N52E, 49.38', fd nail P. Pole
 S33E, 46.18', set nail 8" Cherry
 S52W, 42.45', set nail 8" Cherry



by *Eugene Farrier*

Date 12-22-94

Surveyor's Michigan License No. 24594