

SURVEY & REMONUMENTATION

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:24

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

corners in

KALKASKA (County)	Located In:	Corner Code #
1994 REMONUMENTATION	T 27N R 6W	G-9
Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

EUGENE FARRIER, in a field survey on NOV. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules heretofore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as assessed below:

TE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G-9: Cor. common to Sec. 21, 22, 27 & 28, T27N-R6W
1850 GLO re-survey: set post, Cedar 4", S35E, 38, Tamarak 12", N34W, 21
12-4-02, W.S. Merrill, stmps of Govt bear trees, set Cedar stk, no access
1&8-03, W.S. Merrill, set Cedar Stake, gov't. bear. trees, no access
3-29-06, W.S. Merrill, stumps of orig. bear. trees, no access.
1936, MDOT, Right-of-way map, noted cor., no accessories
1955, K.J. Ostling, set markers N. of rd, w/accessories,
12-27-73, LCRC(N.F. Parker), set 1/2" bar by dble prop. dist, w/access,
2-93, Wilcox Assoc., noted cor., w/access,

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: Cor. common to Sec. 21, 22, 27 & 28, T27N-R6W
Set 5/8" x 18" rebar w/brass cap. 13' N. of C/L M-72 in Mon. Box, 0.25' below surface and 1.0' into bit. shoulder.
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: Cor. common to Sec. 21, 22, 27 & 28, T27N-R6W
Set 5/8" x 18" rebar w/brass cap. 13' N. of C/L M-72 in Mon. Box, 0.25' below surface and 1.0' into bit. shoulder.
N67E, 74.54', set nail in 10" cedar
S08E, 55.09', set nail in 13" cedar
N40W, 69.55', set nail in Power Pole
S33W, 58.88', set nail in 8" quad maple



Recorded by *Eugene Farrier*

Date 12-22-94

Surveyor's Michigan License No. 24594