

SURVEY & REMONUMENTATION

MAR 21 1997

KALKASKA COUNTY, MICHIGAN RECEIVED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:26

For corners in

KALKASKA
(County)

Located In:

Corner Code #

1996 REMONUMENTATION

1. Public Land Survey	T	27N	R	6W	G-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

EUGENE FARRIER, in a field survey on March 8, 19 96,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

3. Description of original monument and accessories and/or subsequent restoration:

- G-11 cor common to Sec. 27, 28, 33 & 34, T27N-R6W, Excelsior Township. 1852, GLO resurvey, Set Post. 12"Hemlock N80W 18, 12"Cedar S35E 27. 1888, E.Mosher, Co. Surveyor, used corner, no accessories.
- 12-04-1902, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 08-27-1903, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 09-02-1903, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 03-29-1906, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 12-12-1912, W.S.Merrill, Co. Surveyor, used corner, no accessories.
- 09-02-1959, K.J.Ostling, set 1" pipe /w 4" brass cap w/ accessories.
- 12-17-1971, J.L.Wilcox, used corner. Liber 2 pg. 53 of Survey.
- 10-02-1975, LCRC Liber 1 pg. 368.
- 10-04-1975, H.L.Fluharty, fd DNR cap & pipe. Liber 1 pg. 762 of Survey.
- 07-21-1992, N.L.Way, used corner, no accessories.

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-11 cor common to Sec. 27, 28, 33 & 34, T27N-R6W, Excelsior Township. Found bent DNR monument w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

Ratified by Peer Group

P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-21-97

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11 cor common to Sec. 27, 28, 33 & 34, T27N-R6W, Excelsior Township. Found bent DNR monument w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap.
- Set nail & tag S53E 6" Maple, 10.22'
- Set nail & tag N87E 6" Maple, 33.25'
- Set nail & tag N23E 4" Balsam, 53.70'
- Found nail & tag N18W Y. Birch stump, 10.08'



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594