

**SURVEY &
REMONUMENTATION**

MAR 21 1997

KALKASKA COUNTY, MICHIGAN
RECEIVED

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PH 2: 26

or corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1996 REMONUMENTATION Public Land Survey	T <u>27N</u> R <u>6W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER in a field survey on March 8, 19 96,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

3-12 cor common to Sec. 33 & 34, T27N-R6W, Excelsior Township.
1852, GLO resurvey, Set Post. 12"Balsawood S53E 16, 12"Balsawood N55W 16
1888, E.Mosher, Co. Surveyor, used corner, no accessories.
19-02-1903, W.S.Merrill, Co. Surveyor, used corner, w/ accessories.
10-20-1959, K.J.Ostling, set 1" pipe w/ 4" brass cap, w/ accessories.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3-12 cor common to Sec. 33 & 34, T27N-R6W, Excelsior Township.
Found DNR monument w/ accessories. No G.L.O. witnesses were found. The
Kalkaska Co. peer group approved & accepted the above monument as a
careful and faithful reestablishment of the position of the original
corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-21-97

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3-12 cor common to Sec. 33 & 34, T27N-R6W, Excelsior Township.
Found DNR monument w/ accessories.
Set nail & tag N20W 10" Cedar, 11.78'
Set nail & tag N70E 4" Ash, 4.73'
Set nail & tag S25W 6" Cedar, 10.90'
Set nail & tag S75W 5" Ash, 18.83'



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 1-30-97