

SURVEY & REMONUMENTATION

MAY 10 1999

KALKASKA COUNTY, MICHIGAN RECEIVED

1994 DEC 23 AM 9:26

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Jean Hall
REG. OF DEEDS

corners in

KALKASKA (County)	Located In:	Corner Code =#
1994 REMONUMENTATION		
Public Land Survey	T 27N R 6W	I-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

EUGENE FARRIER, in a field survey on NOV. 12, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the joint manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as recorded below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

TE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

I-9: Cor. common to Sec. 22, 23, 26 & 27, T27N-R6W
1850 GLO re-survey: set post, Sugar 16", N60W, 33, Sugar 14, S65E, 34
7-1876, D.E. McVee, noted cor., no accessories
8-03 - 3-06, W.S. Merrill; noted cor., no accessories
1936, MDOT, Right-of-way, noted cor., no access.
1955, K.J. Ostling, noted cor., no access.
12-27-73, LCRC(N.F. Parker), fd old 1/2" bar in rd, w/access,
8-8-79, N.F. Parker, fd 1/2" bar, w/accessories, Lib 2 Pg's 386 &387
2-93, Wilcox Assoc., fd 1/2" bar in Mon. box, w/accessories

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9: Cor. common to Sec. 22, 23, 26 & 27, T27N-R6W
Fd 1/2" X 36" re-rod in Mon. Box. Pulled & reset with 5/8" x 18" R.B. & brass cap, 14' North C/L M-72 & 0.6' below grade. No GLO wit. were fd
On 12-20-94 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *[Signature]*

Date 12-20-94

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9: Cor. common to Sec. 22, 23, 26 & 27, T27N-R6W
Fd 1/2" x 36" re-rod in Mon. Box. Pulled & reset with 5/8" x 18" R.B. & brass cap, 14' North C/L M-72 & 0.6' below grade.
N77E, 68.97', face MDOT marker
N33W, 54.63', fd nail P. Pole
S32W, 93.56', fd nail 14" Maple
S20E, 68.58', 5" dia. pipe (ctr) gate post



Recorded by *[Signature]*

Date 12-22-94

Surveyor's Michigan License No. 24594