

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 NR. 6 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 27-28-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" Maple	-	N79W	-	39 1/2 links
9" Maple	-	S66E	-	74 links
8" Cedar	-	S13W	-	68 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial resurvey of this township. Set corner from probable SE government BT, which is only Cedar near to correct position. This point checks stream north, the 36" W. Pine line tree south, and probable Hemlock line tree west. Checks for line over 1/4 and section corner south, and for line and distance to good 1/4 corner north. This point faced by old blazed Cedar NW which could have been an NBT to the corner.

Corner placed and witnessed September 2, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 9/4/59