

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA
(County)
2000 REMONUMENTATION

Located In: _____ Corner Code # _____

1. Public Land Survey

T 27N R 6W D-5

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

**SURVEY &
 REMONUMENTATION**

FEB 26 2001

SECTION

I, EUGENE FARRIER, in a field survey on December 12, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T27N-R6W, Excelsior Township

1852, G.L.O. Resurvey, by George H. Cannon, set post for corner; Ironwood 10", N5°W, 38 Lks; Sugar 14", S50°E, 34 Lks

1895, Survey, by E.B. Dinnis (Co. Surveyor), found brick buried by old stake

1981, LCRC, by D.M. Bongiovanni, Liber 2, Pg 220, found 1/2" iron bar in mon box; found PK nail in 28" Maple, N40°W, 49.57'; found nail in fence post, S08°W, 53.35'; found PK nail in face of fence post, S24°E, 36.30'

1993, Survey, by Kalkaska Co. Rd. Comm., found mon. box; 24" Maple, N40°W, 49.57'; fence post, S8°W, 53.55'; fence post, S24°E, 36.30'

1993, LCRC, by J.D. Geers, Liber 3, Pg 35, found iron; 24" Maple, N35°W, 49.22'; 7" R. Pine, N20°E, 54.20'; 5" R. Pine, S34°E, 80.56'; 4" R. Pine, N63°E, 96.98'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T27N-R6W, Excelsior Township

Found 1/2" iron with cap #14102 in mon box in centerline Highway 612 & centerline Lewis School Road to North. Added brass remon cap No G.L.O. witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T27N-R6W, Excelsior Township

Found 1/2" iron with cap #14102 in mon box in centerline Highway 612 & centerline Lewis School Road to North. Added brass remon cap

N24°E, 54.40'; 12" R. Pine, set nail & tag West side

S48°E, 84.93'; 6" R. Pine, set nail & tag NE side

S23°E, 36.60', fence post, set nail & tag West side

N34°W, 49.26', 30" Maple, set nail & tag SW side

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 2-14-01



Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 2-15-01



3026827
 Page: 1 of 1
 02/18/2001 10:26A
 REMON
 LB: 6 PG: 156