

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code #
<u>1993 REMONUMENTATION</u>	T <u>27N</u> R <u>7W</u>	<u>A-7</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN
 RECEIVED

1993 DEC 22 PM 1:27

Jean Hall
 REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER in a field survey on NOV. 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

A-7 cor. common to Sec. 18 & 19, T27N-R7W, & Sec. 13 & 14, T27N-R8W
 1850 GLO re-survey. Set Pine post, Sp Pine 12", N31E, 35; Sp Pine 9" S34E, 8.
 9-10-68, Survey by Russell L. Roon, (filed in misc. surveys).
 4-20-76, J.L. Fletcher fd 1/2" re-rod Liber 1, Pg 883 of surv.
 1-15-79, LCRC: Liber 2, Page 169.
 10-15-91, C. F. Roser, DNR Surv., Fd. iron w/ accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 cor. common to Sec. 18 & 19, T27N-R7W, & Sec. 13 & 14, T27N-R8W
 Found and accepted 1/2" re-rod w/ oblit. LS cap in C/L black top rd. and 13' West of C/L of rd. to South; (as Recorded in LCRC: Liber 2, Page 169 and DNR accessories).
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 cor. common to Sec. 18 & 19, T27N-R7W, & Sec. 13 & 14, T27N-R8W
 Found 1/2" re-rod w/ oblit. cap, replaced w/ 5/8" re-rod with 3-1/4" Brass Cap
 N45E, 47.45', nail in 7" J. Pine
 N34W, 47.12', nail in 12" J. Pine
 S13W, 41.85', nail in 7" J. Pine
 S58E, 71.40', nail in 6" J. Pine
 S12W, 82.05', nail fd. in 14" R. Pine
 N12E, 33.09', fd. Con. Mon.
 North, 33', DNR wit. post

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 12-22-93