

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA

(County)

1993 REMONUMENTATION

Located In:

Corner Code: #

- | | | | |
|------------------------------------|--------------|-------------|------------|
| 1. Public Land Survey | T <u>27N</u> | R <u>7W</u> | <u>A-8</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:28

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on NOV. 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8 cor. common to Sec. 19, T27N-R7W & Sec. 24, T27N-R8W
1850 GLO re-survey: set post, W. Pine 16", S70W, 7; Y. Pine 12", N80W, 7
9-5-73, J.L. Wilcox, fd 3/4" pipe, Liber 1 Pg 424 of Surv.
9-6-73, LCRC Liber 1 Pg 261.
7-17-91, C.F. Roser, fd 1/2" pipe, DNR survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 cor. common to Sec. 19, T27N-R7W & Sec. 24, T27N-R8W
Found and accepted 1/2" galv. pipe 6' West of C/L gravel & dirt trail, no GLO witnesses fd (believed removed due to close proximity of road and witnesses, witness trees gone from LCRC, Liber 1 Pg 261.
On 12-22-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 cor. common to Sec. 19, T27N-R7W & Sec. 24, T27N-R8W
Found 1/2" galv. pipe - pulled pipe and reset w/ 5/8"x18" re-bar w/ Brass Cap.
N51E, 60.82', 9" J. Pine, fd.
N37E, 68.85', 6" Aspen, fd.
N75E, 70.59', 6" clp. Maple, fd.
N13W, 45.56', 8" J. Pine, fd.
West, 16.5', Cedar Post w/tag, fd.
N22E, 10.43', Schaaf pipe in conc., fd.



Signed by Eugene FARRIER
Surveyor's Michigan License No. 24594

Date 12-22-93