

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

KALKASKA COUNTY, MICHIGAN  
RECEIVED

For corners in

|                                       |                          |               |
|---------------------------------------|--------------------------|---------------|
| <u>KALKASKA</u><br>(County)           | Located In:              | Corner Code # |
| 1993 REMONUMENTATION                  |                          |               |
| 1. Public Land Survey                 | T <u>27N</u> R <u>7W</u> | <u>A-9</u>    |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                          |               |
| 5. Private Claims _____               |                          |               |

1993 DEC 22 PM 1:28

*Jean Hase*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on DEC. 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

A-9 cor. common to Sec. 19 & 30, T27N-R7W, & Sec. 24 & 25, T27N-R8W  
1850 GLO re-survey: Hemlock 12", S62E, 34; Beech 12", N28E 41.  
2-5-73, J.L. Wilcox, fd 4" wood hub, Liber 1 Pg 424 of Surv.  
9-11-73, LCRC Liber 1 Pg 265.  
12-20-73, J.L. Wilcox, set conc. mon., Liber 1 Pg 498 of Surv.  
12-27-73, LCRC Liber 1 Pg 305.  
9-11-89, LCRC Liber 2 Pg 380.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 cor. common to Sec. 19 & 30, T27N-R7W, & Sec. 24 & 25, T27N-R8W  
Found and accepted Conc. Mon. in line with new fnc. to East, fd accessories.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 cor. common to Sec. 19 & 30, T27N-R7W, & Sec. 24 & 25, T27N-R8W  
Found Conc. Mon. - Set Aluminum Cap in conc. on same Conc. Mon. 0.4' above ground.  
S37W, 39.52', 6" Maple (in clump), fd.  
N18W, 79.76', 12" Maple (in clump), fd.  
N69E, 35.11', 8" Maple (in clump), fd.  
S87W, 15.29', 14" Cherry, fd.  
East, 1.40', 6" Cedar Post, fd spk in N. fc.  
South, 1.23', 6" Cedar Post, fd spk in W. fc.

Signed by *Eugene Farrier* Date 12-22-93  
Surveyor's Michigan License No. 24594