

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 KALKASKA COUNTY, MICHIGAN RECEIVED

For corners in

KALKASKA
(County)
1993 REMONUMENTATION

Located In:

Corner Code #

1993 DEC 22 PM 1:28

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>27N</u> R <u>7W</u> | <u>A-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on DEC. 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10 cor. common to Sec. 30, T27N-R7W & Sec. 25, T27N-R8W
1850 GLO re-survey: set Sugar Post Hemlock 30", S24W, 11; Hemlock 36", N33W, 35.
12-20-73, J.L. Wilcox, set conc. mon., Liber 1 Pg 498 of Surv.
12-27-73, LCRC Liber 1 Pg 306.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 cor. common to Sec. 30, T 7N-R7W & Sec. 25, T27N-R8W
Found and accepted 4' Conc. Mon. 0.3' above ground, fd accessories. Stream North 140'.
On 12-16-93 the Kalkaska Co peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 cor. common to Sec. 30, T27N-R7W & Sec. 25, T27N-R8W
Found Conc. Mon. - Set Aluminum Cap in conc. on same Conc. Mon.
N10E, 45.23', 10" Cedar, (fd spk in W. fc.).
N76E, 12.72', 10" Maple, (fd spk in N. fc.).
S57W, 42.64', 14" Birch, (fd spk in SE. fc.).
S17E, 53.27', 10" Maple, (set spk in E. fc.).

Signed by *Eugene Farrier* Date 12-22-93
Surveyor's Michigan License No. 24594