

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:28

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EUGENE FARRIER, in a field survey on NOV. 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-7 cor. common to Sec. 19 & 18, T27N-R7W
- 1850 GLO re-survey: Set post, Y. Pine 12", S57W, 11; Y. Pine 18", 44.
- 6-21-61, Sherman's Subdivision, Liber B, Pg 46, tied to corner.
- 9-10-68, Russell L. Roon RLS, (filed in misc. surveys) fd corner.
- 2-5-73, J. L. Wilcox fd 1/2" rod, Liber 1 Pg 424 of Surv.
- 9-6-73, LCRC Liber 1 Pg 262
- 4-20-76, J.L.Fletcher fd 1/2" re-rod, Liber 1 Pg 883 of Surv.
- 11-77, J.L. Nelson fd 1/2" rod, Liber 2 Pg 49-50 of Surv.
- 5-23-85, N.B.DeYoung fd 1/2" rod, Cert. of Survey
- 3-13-90, E.Farrier fd, Liber 3 Pg 436 of Surv.
- 10-15-91, C.F.Roser, D.N.R. survey, fd iron w/ accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 cor. common to Sec. 19 & 18, T27N-R7W
Found and accepted 1/2" re-rod w/ oblit. LS cap 2.8' S. of C/L black top rd.; (as Recorded in LCRC, Liber 1 Pg 262; Cert. of Surv., Liber 2 Pg 49-50 and DNR accessories).
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 cor. common to Sec. 19 & 18, T27N-R7W
Found 1/2" re-rod w/ oblit. LS cap, replaced w/ 5/8" re-rod with 3 1/4" Brass Cap
S18W, 39.98', nail in 9" J. Pine, fd w/ wit tag #21273
S05W, 32.97', 1/2" re-rod w/ cap #33969
S34E, 79.48', nail in 13" trip. Maple, fd
N44E, 50.27', nail in 8" J. Pine, fd
N05E, 33.00', conc. mon.

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-93