

SURVEY &  
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located in:	Corner Code #
1993 REMONUMENTATION	T <u>27N</u> R <u>7W</u>	<u>B-11</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

KALKASKA COUNTY, MICHIGAN  
RECEIVED

1993 DEC 22 PM 1:28

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						

I, EUGENE FARRIER, in a field survey on DEC. 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-11 cor. common to Sec. 30 & 31, T27N-R7W  
1850 GLO re-survey: set Post Hemlock 18", S20W, 31; Hemlock 10", N42W 13.  
9-30-1887, E. Mosher, Co. Surv., visited cor. no accessories.  
5-16-07, W.S Merrill, Co. Surv., visited cor. no accessories.  
MSHD, tied cor. with survey for U.S. 131.  
9-12-72, LCRC Liber 1 Pg 154, fd old plow point.  
12-1972, N.F. Parker, Survey for Northern Mich. Gas, dwg #S-G 17506.  
6-15-72, N.F. Parker, fd plow point, Liber 1 Pg 251 of Surv.  
5-7-75, J.L. Wilcox, fd plow point, Liber 1 Pg 957 of Surv.  
2-22-78, J.L. Wilcox, Liber 2 Pg 296 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 cor. common to Sec. 30 & 31, T27N-R7W  
Found and accepted 3/4"x24" iron-pipe w/cap #10695 in line w/old road cut to East, GLO witnesses fell in Highway fill area, no plow pt. fd.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 cor. common to Sec. 30 & 31, T27N-R7W  
Found 3/4"x24" iron pipe - pulled and set 5/8"x36" re-bar w/ Brass Cap 0.4' below surface.  
N58W, 50.80', Old W. Pine stump, fd.  
N5E, 47.32', 8" Tamarak, set nail.  
S75W, 42.21', 10" Maple, set.  
N65W, 85.39', 6" Maple, set.  
N84W, 80.42', W. Cor. on re-bar in R/W Mon.  
S40E, 38.00', C/L U.S. 131.

Signed by *Eugene Farrer*  
Surveyor's Michigan License No. 24594

Date 12-22-93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 197  
REVISED MAY 14, 197  
REVISED JAN., 198