

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 KALKASKA COUNTY, MICHIGAN
RECEIVED

For corners in

<u>KALKASKA</u> (County) 1993 REMONUMENTATION	Located In:	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 22 PM 1:29

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-7 cor. common to Sec. 17, 18, 19 & 20, T27N-R7W
1850 GLO re-survey: Set post, W. Pine 20", S21E, 34; W. Pine 20", N68W, 68.
1908, W.S. Merrill, Co. Surveyor visited cor. original Gov. Bearing trees.
5-52, A.L. Dragoo, Co. Surv. fd bottom of original stake, set 2" iron pipe
6-21-61, Sherman's Subdivision, Liber B Pg 46.
5-15-69, Whipple's Subdivision, Liber D Pg 11.
10-12-72, J.L. Wilcox fd 3" gas pipe, Liber 1 Pg 242 of Surv.
10-12-72, LCRC Liber 1 Pg 149.
2-1-74, D.R. Verba fd 2" pipe, Liber 1 Pg 473-475 of Surv.
8-1-77, J.I. Nelson fd 3" pipe, Liber 2 Pg 49-50 of Surv.
11-26-76, J.L. Fletcher fd 3" gas pipe, Liber 1 Pg 944 of Surv.
5-25-85, N.B. DeYoung, fd 3" gas pipe, Cert. of Surv.
10-10-89, J.L. Schwandt, fd 3" gas pipe, Liber 3 Pg 331 of Surv.
3-13-90, E. Farrier, fd 3" gas pipe, Liber 3 Pg 436 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 cor. common to Sec. 17, 18, 19 & 20, T27N-R7W
Found and accepted 3" gas pipe; (as Recorded in LCRC; Liber 1 Pg 149 and previous Cert. of Surveys). GLO witnesses fell in road cut.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

C-7 cor. common to Sec. 17, 18, 19 & 20, T27N-R7W
Found 3" gas pipe, placed 5/8"x18" re-rod w/ Brass Cap in center of pipe.
North, 14.4', C/L road intersection.
N52E, 94.70', 20" R. Pine, set new spk.
N44W, 74.67', 8" Maple, set new spk.
S20W, 70.77', P. Pole.
S18E, 68.12', 10" S. Pine, fd.
S84W, 145.58', 36" Maple, set new spk.

Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-93